

CAR MANUFACTURING PLANT IN THE UK



PROJECT DESCRIPTION His project included several BiW installations.

22x PLC Rockwell Automation Compact Logix / 122 ABB IRC 5 Robots, quantity I/O: ± 26 400, I/O local via ethernet, SEW movipro / movidrive, Electromechanical technology: welding, handling, stapling and gluing robots (ABB IRC5), transport, turning plates, light fixtures, electrical design with E-plan P8 / Sistema, software engineering, OLP, virtual commissioning, installation, manufacturing of boards, control panels and decentralised boards, start-up (PLC and Robot) + production support, training.

